ENGINEERING DEPARTMENT

BUREAU OF SANITARY ENGINEERING, BANGALORE.

Notification dated 10th October 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M., on 7th November 1936, for constructing drains in Magadi Town (Second Stage). An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1937.

2. The plans, and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash (no cheques will be accepted) as earnest money, and be superscribed "Tender for constructing drains in Magadi Town (Second Stage)" in default of which the tenders will be rejected.

5. The final acceptance of the tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Director of Health will be final and legally binding.

ESTIMATE OF APPROXIMATE QUANTITIES OF WORK.

No.	Particulars	Unit	Quantity
1	Constructing silk pattern drain with 3″ burnt stone slabs cheeks and surki concrete bed by forming a channel at the centre of concrete bed, surface plastered over with ½″ cement mortar and joints of slabs cement pointed inculding earthwork excavation for the drain as per type design :—		
	2″ Section drain with available old slabs	Rft.	2,800
	3″ Section drain with new slabs	,,	330
	4″ (2) Section drain with new slabs	,,	400
	5″ (2) Section drain with new slabs	,,	420
	6″ (3) Section drain with new slabs	,,	100
2	Dismantling rough stone revetment of existing box drain and stocking	Cyds.	270
3	Removing and refixing the old covering slabs 4″ to 6″ thick over the drain	Sft.	1,500
4	Removing the old slabs 4″ to 6″ thick in front of houses for constructing the silk pattern drains..	,,	3,000

Notification dated 16th October 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 1 P.M. on 7th November 1936, for Constructing drains in Chamarajanagar Town (3rd Stage). An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans and conditions may be seen at the Sanitary Engineer's Office between the hours of 11 A.M. and 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 520 in cash (no cheques will be accepted) as earnest money, and be superscribed " Tender for constructing drains in Chamarajanagar Town (3rd Stage) " in default of which the tender will be rejected.

5. The final acceptance of any tender will rest with the Sanitary Engineer in Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Sanitary Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Sanitary Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Directer of Health will be final and legally binding.

ESTIMATE OF APPROXIMATE QUANTITIES OF WORK.

No.	Particulars	Unit	Quantity
I	Constructing silk pattern drain with 3″ burnt stone slab cheeks and surki concrete bed by forming a channel at the centre of concrete bed, surface plastered over with $\frac{1}{2}$″ cement mortar and joints of slabs cement pointed including earthwork excavation for the drain—		
	(*a*) 2″ Section drain with new stone	R.ft.	490
	(*b*) 2″ Section drain with old slabs by removing old slabs and cutting to the required size	,,	820
	(*c*) 3″ Section drain with new slabs	,,	1,840
	(*d*) 7″ (2) Section drain with new slabs	,,	1,190
II	Constructing main drain $\frac{2\frac{1}{2}' + 3\frac{1}{2}'}{2} \times 2\frac{1}{2}'$ in size stone in surki mortar on one foot thick surki concrete bed by forming $1\frac{1}{4}'$ diameter semi circular channel at the centre of bed, the curved surface of the bed being plastered with $\frac{1}{2}$″ cement plastering and flat surface covered with 3″ burnt stone slabs and cement pointed the joints of slabs and walls. The dimensions of the side walls are $1\frac{1}{2}'$ at top and 2′ at bottom—as per type design	,,	180
III	Removing and relaying burnt stone slabs of the drains in front of houses	S.ft.	2,197

No.	Particulars	Unit	Quantity
IV	Removing and refixing old slabs over the tunnel at road crossing ..	S.ft.	795
V	Earthwork excavation	C.yd.	228
VI	Stone jelly concrete with surki mortar	C.ft.	2,503
VII	Size stone in surki mortar	,,	1,912
VIII	Cement pointing	Sqr.	10·23
IX	½" thick cement plastering	Sqr.	76·29
X	Providing burnt stone slabs 6" thick for the tunnels with rough dressing	S.ft.	700
XI	Carting surplus earth a lead of half a mile	C.yd.	300
XII	Removing and stacking rough stone revetment with half mile lead.	,,	200
XIII	Cement pointing to existing rough stone masonry of the drain ..	Sqr.	53·20
XIV	Scraping old cement plastering and cleaning	,,	97·32

B. R. GARUDACHAR,
Sanitary Engineer.

BANGALORE DIVISION.

Abstract Notification datad 8th October 1936.

The attention of the public is invited to the detailed Notification, inviting tenders for Restoring Bannaghalli Chickere, Register No. 173 of Chennapatna Taluk, published on pages 1693-1694 of Part VI of the *Mysore Gazette*, dated 15th October 1936.

The last date for the receipt of the tender is 2 P.M., on 2nd November 1936 and the earnest money to accompany the tender is Rs. 200.

Notification dated 15th October 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 2nd November 1936, for the maintenance work to Sannanhalli Thavarekere, Magadi Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposited of Rupees two hundred (Rs. 200) in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for the maintenance work to Sannanhalli Thavarekere, Magadi Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.